

CONTENTS

<i>Acknowledgments</i>	<i>xi</i>
<i>About the Authors</i>	<i>xiii</i>
<i>Preface</i>	<i>xv</i>
1. What Is an Offshore Wind Farm?	1
Monopile	3
Gravity Base	3
Tripod	4
Jacket	5
2. Obtaining Permits for Wind Farms	9
The United States	9
The United Kingdom	17
Germany	20
3. Project Planning	31
Project Strategy Outline	31
The Project Execution Plan	36
Start of Production	40
Tender and Contract Strategy	46
QA and QC Requirements	48
Human Resources for Installations	49
4. The Basic Organization	55
Sales	56
Planning	59
QA and HSE	61
Project Management	66
Service Department	70
Technical Management	71
5. Project Preparation	75
Define Project Parameters	75
Contracting Products and Services	79
Developing Project HSE Plans and Procedures	80
Developing QA/QC Plans and Procedures	81

Determining Methods and Required Equipment	82
Defining the BOP	82
Creating the Final Project Time Schedule	84
Implementing Plans and Procedures for Suppliers and Contractors	88
Preparing On- and Offshore Construction Sites	88
6. Project Execution	95
Auditing	95
Project Startup Sequence	98
Monitoring the Activities	102
Project Management Setup	103
7. Interface Management	119
The Main Interfaces and Accompanying Responsibilities	119
Contracting to an EPC Contractor	125
The Economy	131
Interfaces and Handover Documents	132
8. Health, Safety, and Environmental Management	149
Why HSE Management is Important	149
The HSE Documentation Structure	151
The HSE and National Authorities	159
9. Work Vessel Coordination	163
Organization Setup and Functions	163
The Operations Center and the Work Carried Out	165
Organization of Surveillance	167
10. Logistics Solutions	171
11. Commonly Used Installation Methods	177
Foundations	177
Tripod Foundations	184
Installing Foundations	185
Important Things to Consider	190
12. Vessels and Transport to Offshore Installations	203
Types of Vessels	203
Tradeoffs When Choosing a Particular Vessel	206
Assessing Equipment	209
Basic Information about Ports	234

13. Operation and Maintenance	243
Introduction	243
Looking Back: What Have We Learned?	245
Moving to Offshore	250
Operations and Maintenance: The Support Facility	270
Balance of Plant and Subsea Requirements	273
Operations and Maintenance: Resources	279
Operations and Maintenance: The Future	279
 14. Project Criteria	 285
Offshore Access Systems	285
Waves	287
Wind	289
Currents	289
 15. Transporting Wind Turbines	 293
Types of Transport Vessels	294
Transfer Systems	303
 16. Deployment Strategies	 311
Shared Access to Offshore Equipment	312
Future Trends in the Service Vessel Industry	315
Crew Vessel Selection Criteria	316
Basic Information Relating to Crew Vessels	319
 17. Repairing Offshore Wind Farms	 327
How Does It Work?	328
 18. Environmental and Other Issues	 331
Protecting the Environment	331
Waste Management	333
Pollution Issues	335
The Working Environment	339
Piling Noise	339
Cofferdams	343
 <i>Conclusions About O&M Transport Systems</i>	 <i>353</i>
<i>Decommissioning of Wind Turbines</i>	<i>359</i>
<i>Final Thoughts</i>	<i>365</i>
<i>Index</i>	<i>367</i>